Cleveland	216.901.0000	
Columbus	614.431.3000	
Detroit	313.309.9000	
Pittsburgh	412.809.8100	
Toll Free	877.901.0000	

After hours Call any of the numbers above and press Option 2; leave a message and we will respond shortly.

eventsource.com

Instructions carpetdeck tile

Area Preparation

It is recommended that sensitive wooden gym floors be swept or cleaned prior to installation of CarpetDeck. This removes dirt and debris from the surface prior to installation.

Installation

Each CarpetDeck tile is approximately 21.67 sq/ft (40"x 78"). It is recommended that the CarpetDeck transport cart be used for installation as it speeds laying of tiles considerably. Tiles should be laid lengthwise (see diagram below), with all tiles facing the same way (on the bottom of each tile is an arrow indicating the direction of each tile). This will ensure that the carpet weave is uniform. Begin by laying tiles in rows starting at one end and moving along a single row. It is important that the first row of tiles be at an exact 90° angle to the direction of the floor to prevent "drifting" of the floor over distance.

1	2	3	4
5	6	7	etc.

Video

See our team installing carpetdeck tile at: https://vimeo.com/217018191

