

# CARPETDECK TILE



## INSTRUCTIONS

---

### STEP 1

Sweep/clean sensitive wooden gym floors before installing Carpetdeck to remove dirt and debris.

### STEP 2

Each CarpetDeck tile is approximately 21.67 sq. ft. (40"x 78"). Use the CarpetDeck transport cart for installation to speed up the installation process. Lay the tiles lengthwise, with all tiles facing the same way (an arrow is on the bottom of each tile indicating the correct direction). This will ensure the carpet weave is uniform.

### STEP 3

Lay tiles in rows starting at one end and moving along a single row. It is important that the first row of tiles be at an exact 90° angle to the direction of the floor to prevent "drifting" of the floor over distance.

### AFTER HOURS:

Contact your local branch.

---